



EQUIPMENT SCHEDULE:

1. WALL MOUNTED FLYKILLER.
2. WALL MOUNTED WASH HAND BASIN.
3. PREPARATION CUPBOARD BENCH.
4. WALL MOUNTED LOCKABLE CUPBOARD.
5. EXISTING - WATER BOILER.
6. SHAPED PREPARATION BENCH.
7. DOMESTIC OPEN TOP OVEN RANGE - CLIENT SUPPLY.
8. EXTRACTION CANOPY.
9. PREPARATION BENCH/SINGLE DRAWER UNDER.
10. EXISTING - CENTRE TABLE.
11. SPARE NO.
12. UNDERCOUNTER FREEZER. (MOUNTING KIT)
13. UNDERCOUNTER FRIDGE. (STACKED)
14. CUSTOM TALLBOY STORAGE CUPBOARD/OPEN VOID UNDER.
15. UNDERCOUNTER FRIDGE.
16. PREPARATION BENCH/OPEN VOID UNDER.
17. WALL MOUNTED LOCKABLE CUPBOARD.
18. SPARE NO.
19. SPARE NO.
20. CUSTOM TALLBOY COSSH CUPBOARD.
21. FRONT LOAD DISHWASHER.
22. LOW LEVEL STAND/BASKET RUNNERS UNDER.
23. DOUBLE BOWL SINK UNIT.
24. PRE-RINSE SPRAY UNIT.
25. SPARE NO.
26. SPARE NO.
27. SERVERY COUNTER COMPRISING:
 - A. PLAIN WORKTOP/OPEN STORAGE UNDER.
 - B. HEATED BAINMARIE/HOTCUPBOARD BASE.
 - C. PLAIN WORKTOP/OPEN STORAGE UNDER.

DENOTES WALLS TO BE FITTED WITH WHITE ROCK

GENERAL DRAWING NOTES

- NOTE 1 : ALL INCOMING SERVICES TO BE PROVIDED BY SUITABLY QUALIFIED PERSONNEL TO CONFORM WITH CURRENT LEGISLATION. TO HAVE APPROPRIATE STOPCOCKS, SWITCH FUSE ISOLATORS AND OUTLETS ETC.
- NOTE 2 : CONTRACTOR TO BRING THEIR SERVICES TO THE POINTS SHOWN AND LEAVE SUITABLY TERMINATED WITHIN ONE METER OF EACH INDIVIDUAL APPLIANCE.
- NOTE 3 : WATER & WASTE - TO COMPLY WITH CURRENT REGULATIONS & BYLAWS. TO INCLUDE BACKFLOW PREVENTION AS PER "WRAS" CATEGORIES 3, 4, & 5.
- NOTE 4 : POTABLE WATER CONNECTIONS ARE ALL "WRAS" APPROVED.
- NOTE 5 : VENTILATION TO COMPLY WITH CURRENT DW172 REGULATIONS & BYLAWS.
- NOTE 6 : MECHANICAL EXTRACTION SYSTEMS MUST BE INTERLOCKED WITH THE GAS SUPPLY.
- NOTE 7 : ALL WIRING TO MEET CURRENT IEE REGULATIONS.
- NOTE 8 : ALL EARTH BONDING BY ELECTRICAL CONTRACTOR.
- NOTE 9 : NO GREASE TREATMENT SOLUTION IS INCLUDED UNLESS OTHERWISE STATED.
- NOTE 10 : FAILURE TO PROVIDE SERVICES AS DETAILED MAY RESULT IN SCOMAC BEING UNABLE TO INSTALL THE APPLIANCES.
- NOTE 11 : TO ALLOW DELIVERY INTO THE KITCHEN AREA FROM OFF-LOADING POINT, THE MINIMUM FREE ACCESS WIDTH MUST NOT BE LESS THAN 900mm.
- NOTE 12 : ALL DIMENSIONS ARE SUBJECT TO SITE SURVEY.
- NOTE 13 : ALL FABRICATION TO BE APPROVED PRIOR TO MANUFACTURE.
- NOTE 14 : DO NOT SCALE DRAWING.
- NOTE 15 : THE COPYRIGHT OF THIS DRAWING IS RETAINED BY SCOMAC CATERING EQUIPMENT LTD. REPRODUCTION IN WHOLE OR PART WITHOUT PERMISSION IN WRITING FROM SCOMAC CATERING EQUIPMENT LTD WILL BE CONSIDERED COPYRIGHT INFRINGEMENT.

EXCLUSIONS - UNLESS OTHERWISE STATED

- BUILDERS WORK.
- CANOPY IN-FILLS.
- PLANT & DUCTING.
- GAS & ELECTRICAL WORKS.
- SPECIALIST LIFTING EQUIPMENT.
- REMOVAL OF PLASTIC COATINGS.
- WIRING OF LIGHTS TO OTHER CONTRACTORS CIRCUITS.
- SPECIALIST ACCESS EQUIPMENT.
- RETURN SITE VISITS.
- PLUMBING WORKS.
- FROST PROTECTION.
- GAS HEATER & WATER COIL CONNECTIONS.
- COMMISSIONING IF NOT AT TIME OF INSTALLATION.
- GAS INTERLOCK VALVES.
- DISTRIBUTION BOARDS & SDU'S.
- EMERGENCY KNOCK OFF BUTTON SUPPLY ONLY. CONNECTION BY ELECTRICAL CONTRACTORS.
- GASTRONORM PANS.

EXISTING EQUIPMENT TO BE RE-POSITIONED & RE-USED - SERVICE REQUIREMENTS & DIMENSIONS TO BE CONFIRMED BY OTHERS.

REVISIONS

- REV : "A".. DATE : 05/11/20.. BY : JR..
 REVISE LAYOUT AS COMMENTS 03/11/20..
- REV : "B".. DATE : 04/12/20.. BY : ND..
 REVISE LAYOUT AS COMMENTS 04/12/20..

**Crown Church
Inverness
Proposed Kitchen Area**



THE NAME THAT MEANS EVERYTHING TO CATERERS

ScoMac Catering Equipment Limited.
 1 Bell Square,
 Brucefield Industry Park,
 Livingston, West Lothian.
 EH54 9BY.
 Tel - 01506 426 200
 Email - info@scomaccateringequipment.com
 Web - www.scomaccateringequipment.com

Project	CROWN CHURCH, INVERNESS. PROPOSED KITCHEN LAYOUT.	By	JR.
		Date	29/09/20.
		Scale	1 : 20 @ A2.
Client	CROWN CHURCH. KINGSMILLS ROAD, INVERNESS. IV2 3JT.	Rev	"B"
Dwg	EQ 000000	Sheet	Status

PART OF THE UNITECH GROUP